No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
3	Earthwork Excavation for foundation in stiff soft rock	C.yd.	0 6 0	331	
4	Stone jelly concrete in cement mortar 1 : 6 ..	C.ft.	0 4 6	448	
5	Size stones in cement mortar 1 : 6	,,	0 6 6	715	
6	Burnt stone slabs 6" thick dressed and fixed ..	Sq.ft.	0 8 0	397	
7	Providing pin slabs to be fixed in concrete in cement mortar	,,	0 12 0	68	
8	Cement pointing to exposed masonry	Sqr.	3 8 0	6.00	
9	Rough stone apron with jelly packing and wedging.	C.yd.	1 12 0	68	
10	Removing and resetting old apron with new jelly packing and wedging	,,	0 12 0	79	
11	Providing joggle joints	Each	1 0 0	11	
	Constructing Right Waste Weir.				
1	(*a*) Earthwork :—Approach and draft clearing up to R. L. 46.00 in all soils	C.yd.	0 4 0	1,219	
	(*b*) Do in soft rock exposed ..	,,	0 6 0	563	
2	(*a*) Earthwork excavation in hard gravelly soil ..	,,	0 4 0	1,028	
	(*b*) Do in soft rock	,,	0 6 0	1,368	
3	Stone jelly concrete in cement mortar 1 : 6 ..	C.ft.	0 4 6	2,114	
4	Size stones in cement mortar 1: 6	,,	0 6 6	5,083	
5	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 8 0	568	
6	Cement concrete slab over toe wall including cement plastering	C.ft.	0 14 0	127	
7	Cement pointing to masonry	Sqr.	3 8 0	24·41	
8	Providing joggle joints	Each	1 0 0	31	
9	Rough stone apron including jelly packing and wedging	C.yd.	1 12 0	1,013	
10	Removing and resetting old stone work with new jelly packing, etc.	,,	0 12 0	178	
11	Jelly filling below apron with one mile lead ..	,,	1 0 0	222	
	Repairing Sluice No. I.				
1	Cutting open the bund for examining the masonry with refilling, watering and consolidation, etc.	C.yd.	..	..	

P. SUBBA RAO,
Executive Engineer.

KADUR DIVISION.

Notification dated 27th March 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, up to 3 P.M. on 15th April 1939 for the work of constructing drains in Chikmagalur town during 1938-39 and 39-40.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kadur, Division, should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, in a sealed cover and superscribed as "Tender for the work of constructing drains in Chikmagalur town during 1938-39 and 1939-40." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury challan for Rs. 1,075 (Rupees one thousand and seventy five only) for having credited this earnest money to 17 (a) P. W. Deposits in any approved Government Treasury. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit will not carry any interest. Tenders unaccompanied by earnest money will not be accepted.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 15th April 1939 at Chikmagalur. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chikmagalur, on all working days, between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 100 per fortnight which will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. Chamudi brand cement must be used for the work.

23. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for constructing drains in Chikmagalur Town during 1938-39 and 1939-40.

No.	Items of work	Unit	Rate	Quantity	Cost
	I. Street drains.				
1	Constructing sylk pattern 3″ drains, including providing and fixing new 3″ thick check slabs dressed, on 4½″ surki concrete bed with 1:6 cement combination mortar and cement plastering ½″ (1:3) proportion complete	R.ft.	..	4,164	
2	Constructing sylk pattern drains 3″ with old burnt stone slabs including cutting longitudinally, dressing, removing and resetting, conveying and fixing on 4½″ surki concrete bed (1:6) cement combination mortar and cement plastering ½″ thick (1:3) proportion complete.	R.ft.	..	4,347	
3	Constructing road crossing with size stone in lime mortar abutments and 6″ thick burnt stone slabs covering complete	No.	..	11	
4	Raising the sides of drain wherever necessary; size stone in mortar	C.ft.	..	..	
5	Dismantling and resetting the steps of houses ..	S.ft.	..	..	
6	Putting extra stone jelly concrete in surki mortar for the bed of drains wherever the soil is soft ..	C.ft.	..	..	
	II. Collecting and Main Drains.				
1	Constructing silk pattern drains with 3″ thick burnt stone new check slabs dressed and fixed on 4½″ surki concrete bed (1:6) cement combination mortar including cement plastering ½″ thick (1:3) proportion complete:—				
	(*a*) 7″ (2) section	R.ft.	..	750	
	(*b*) 6″ (3) section	,,	..	515	
	(*c*) 5″ (2) section	,,	..	1,605	
	(*d*) 4″ (2) section	,,	..	1,645	
	(*e*) 4″ (1) section	,,	..	500	
2	Constructing road crossings with size stone in lime mortar abutments and 6″ new burnt stone slabs covering, etc., complete	No.	..	11	
3	Constructing storm water overflows	No.	..	3	
4	Raising the side of drains with stone in lime mortar wherever necessary	C.ft.	..	..	
5	Putting extra stone jelly concrete in surki mortar wherever soil is soft	C.ft.	..	..	
6	Dismantling and resetting steps of houses ..	S.ft.	..	..	
7	Earthwork cutting roads and forming and refilling where needed	C.yd.	..	..	

C. R. IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, dated 19th November 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.